FIRE RELIEF SERVICES

All Types of Industrial Fire Safety Service

Demonstration letterhead - replace with your verified company address
Demo contact information

QUOTATION

Quotation No: DEMO-QUO-2026-000001 / R1 **Date: 31.10.2026**

To: Demo Courtyard Enclave Vadodara, Gujarat - demonstration site	**Demo site contact** Phone: Demo phone

Sub: Supply and installation of fire hydrant line, fire alarm system, sprinklers, fire extinguishers and accessories

PREVIEW - NOT ISSUED

Sr. No.	DESCRIPTION	MAKE / MODEL	UNIT	Qty.	Supply	Installation	20%	Miscellaneous	Rate	Amount
A	**PUMP HOUSE EQUIPMENT**									
1	**Electric fire pump** Supply, installation, testing & commissioning of horizontal centrifugal single stage fire pump with squirrel cage induction motor (TEFC), mounted on common MS base frame with necessary fittings and accessories. **Head: 70 m** **Discharge: 1620 LPM**	KIRLOSKAR	Nos	1	135000	8000	28600	0	171600	**1,71,600.00**
2	**Diesel fire pump set** Supply, installation, testing & commissioning of diesel engine complete with fuel tank, battery, control panel, exhaust system, and all standard accessories as required. **Head: 70 m** **Discharge: 1620 LPM**	KIRLOSKAR	Nos	1	321000	8001	65800.2	0	394801.2	**3,94,801.20**
3	**Jockey fire pump** Supply, installation, testing & commissioning of horizontal centrifugal single stage fire pump with squirrel cage induction motor (TEFC), mounted on common MS base frame with necessary fittings and accessories. **Head: 70 m** **Discharge: 180 LPM**	KIRLOSKAR	Nos	1	46500	3500	10000	0	60000	**60,000.00**
4	**Pump control panel** Supply, installation, testing & commissioning of Control Panel fabricated out of 14 SWG CRCA sheet steel, modular construction, floor mounted, front operated type, with provision for top and bottom cable entry, suitable for operation of: Main Fire Pump – 1, Jockey Pump– 1 & diesel engine -1 **construction: 14 SWG CRCA** **configuration: 1 main, 1 jockey, 1 diesel**	C&S	Nos	1	53500	4500	11600	0	69600	**69,600.00**
5	**Pump wiring lot** Supply, installation, testing & commissioning of Stranded Copper Conductor, Pvc Insulated Pvc Sheathed, Aluminium Mylar Tape Shielded For Pump Wire.(up to 10 mtr) **Length: 10 m** **conductor: Stranded copper**	Unbranded	Lot	1	16500	3500	4000	0	24000	**24,000.00**
	GI B-Class pipe Supply, installation, testing & commissioning of G.I. 'B' Class pipeline as per relevant IS specifications, complete with necessary fittings such as sockets, bends, elbows, tees, plugs, nipples, flanges, reducers, etc., including cutting, welding, jointing, painting, and all accessories required for proper completion of work. **class: B** **material: GI**	ASIAN								
6	**Nominal diameter: 100 mm**		Mtrs	24	1045	320	273	25	1663	**39,912.00**
7	**Nominal diameter: 80 mm**		Mtrs	6	740	240	196	25	1201	**7,206.00**
8	**Nominal diameter: 65 mm**		Mtrs	20	580	200	156	25	961	**19,220.00**
9	**Nominal diameter: 50 mm**		Mtrs	20	450	160	122	25	757	**15,140.00**
10	**Nominal diameter: 25 mm**		Mtrs	70	225	80	61	40	406	**28,420.00**

Sr. No.	DESCRIPTION	MAKE / MODEL	UNIT	Qty.	Supply	Installation	20%	Miscellaneous	Rate	Amount
11	**Foot valve with SS screen 100 mm** Supply, installation, testing & commissioning of Foot Valve with SS screen, complete with flanged ends and accessories. **Nominal diameter: 100 mm**	KARTAR	Nos	1	4840	400	1048	400	6688	**6,688.00**
12	**Ball valve** Supply, installation, testing & commissioning of Ball Valve	Unbranded	Nos	2	360	50	82	0	492	**984.00**
13	**Air release valve** Supply, installation, testing & commissioning of Air Release Valve (25 mm dia) on top of each riser. **Nominal diameter: 25 mm**	Unbranded	Nos	1	650	50	140	0	840	**840.00**
	Butterfly valve Supply, Installation, Testing and Commissioning of heavy-duty, lever-operated Butterfly Valve, designed for reliable flow control. The valve shall be supplied complete with matching flanges, high-tensile nuts, bolts, and washers, ensuring a leak-proof joint	KARTAR								
14	**Nominal diameter: 100 mm**		Nos	3	1880	400	456	400	3136	**9,408.00**
15	**Nominal diameter: 80 mm**		Nos	1	1530	300	366	300	2496	**2,496.00**
16	**Nominal diameter: 65 mm**		Nos	1	1350	250	320	250	2170	**2,170.00**
	CIDF non-return valve Supply, Installation, Testing and Commissioning of Cast Iron Double Flanged (CIDF) Non-Return Valve with robust metal internals and rubber sealing, conforming to relevant IS specifications. The valve shall be supplied complete with matching flanges, nuts, bolts, and washers, ensuring a tight and durable connection	KARTAR								
17	**Nominal diameter: 100 mm**		Nos	2	2095	400	499	400	3394	**6,788.00**
18	**Nominal diameter: 80 mm**		Nos	1	1495	300	359	300	2454	**2,454.00**
19	**MS structural pipe support** Supply, Installation, Testing and Commissioning of Mild Steel (MS) structural members for supporting the fire hydrant pipeline network, fabricated and fixed from wall to wall as per site requirements. The supports shall be complete with necessary anchor fasteners, clamps, and allied fittings. **material: Mild steel**	Unbranded	kg	80	75	30	21	0	126	**10,080.00**
									TOTAL OF PUMP HOUSE EQUIPMENT	**8,71,807.20**
B	**HYDRANT**									
20	**SS single-headed hydrant valve** Supply, Installation, Testing and Commissioning of Stainless Steel Hydrant Valve conforming to IS: 5290, Type-A, single-headed, with 63 mm dia. female outlet, oblique pattern. The valve shall be provided complete with flange inlet, matching nuts, bolts, washers, and blank cap with chain. The assembly shall be ISI-marked, pressure-tested,complete in all respects **Nominal diameter: 63 mm** **standard: IS 5290 Type A**	EAGLE	Nos	1	2050	250	460	40	2800	**2,800.00**
21	**Single-door MS hose box** Supply, Installation, Testing and Commissioning of Mild Steel (MS) Hose Box, single-door type, suitable for accommodating 1 length of 15 mtr. fire hose pipe along with 1 branch pipes. The unit shall be provided with a front operable glass door and a separate glass provision for key access. The box shall be duly powder-coated/painted in Fire Red colour, complete with locking arrangement and all necessary hardware, installed complete in all respects. **material: Mild steel** **configuration: One 15 m hose and branch pipe**	Unbranded	Nos	1	850	50	180	40	1120	**1,120.00**
22	**RRL fire hose with SS couplings** Supply, Installation, Testing and Commissioning of 63 mm dia. x 15 m RRL Hosepipe as per IS: 636, complete with SS male & female instantaneous couplings, ISI-marked, pressure-tested, and ready for use, complete in all respects. **Nominal diameter: 63 mm** **Length: 15 m** **standard: IS 636**	EAGLE	Nos	1	1900	50	390	40	2380	**2,380.00**
23	**SS branch pipe and nozzle** Supply, Installation, Testing and Commissioning of Stainless Steel (SS) Branch pipe with Nozzle, conforming to IS: 903, complete, pressure-tested, and ready for firefighting use, installed complete in all respects. **material: Stainless steel** **standard: IS 903**	EAGLE	Nos	1	580	50	126	40	796	**796.00**

Sr. No.	DESCRIPTION	MAKE / MODEL	UNIT	Qty.	Supply	Installation	20%	Miscellaneous	Rate	Amount
24	**Hose reel drum** Supply, Installation, Testing and Commissioning of Hose Reel Drum with 30 m hose, shut-off nozzle, and all accessories, conforming to relevant standards, pressure-tested and ready for firefighting use, installed complete in all respects. **Length: 30 m**	EAGLE	Nos	1	2950	350	660	40	4000	**4,000.00**
25	**Two-way fire brigade inlet** Supply, Installation, Testing and Commissioning of 2-way Fire Brigade Inlet with CI body and GM couplings, pressure-tested, durable, and ready for firefighting use, installed complete in all respects. **configuration: Two-way** **material: CI body, GM couplings**	EAGLE	Nos	1	1700	400	420	50	2570	**2,570.00**
26	**Pressure gauge with isolation valve** Supply, Installation, Testing and Commissioning of 100 mm dial size pressure gauge, complete with isolation valve and all necessary accessories, tested and ready for use, installed complete in all respects. **Dial size: 100 mm**	MAHAVIR	Nos	1	550	50	120	0	720	**720.00**
27	**Automatic pump pressure switch** Supply, Installation, Testing and Commissioning of Pressure Switches for automatic operation of pumps, complete with necessary accessories, tested and fully operational, installed complete in all respects.	DENFOOS	Nos	3	900	50	190	0	1140	**3,420.00**
28	**ABC fire extinguisher** Supply, Installation, Testing and Commissioning of 6 kg ABC type fire extinguisher, ISI-marked, fully charged, with all necessary accessories and mounting brackets, ready for use, installed complete in all respects. **Capacity: 6 kg** **agent: ABC dry powder**	SAFEPRO	Nos	3	690	50	148	0	888	**2,664.00**
29	**CO2 fire extinguisher** Supply, Installation, Testing and Commissioning of 4.5 kg CO_2 type fire extinguisher, ISI-marked, fully charged, with all necessary accessories and mounting brackets, ready for use, installed complete in all respects. **Capacity: 4.5 kg** **agent: CO2**	SAFEPRO	Nos	1	2900	50	590	0	3540	**3,540.00**
30	**Fire sprinkler** SITC of SPRINKLER	Unbranded	Nos	50	80	50	26	50	206	**10,300.00**
									TOTAL OF HYDRANT	**34,310.00**
C	**FIRE APPLIANCES**									
31	**Fire alarm panel** Supply, Installation, Testing and Commissioning of Fire Alarm Panel, complete with all necessary accessories, wiring, and connections, fully tested and operational, installed complete in all respects.	AGNI	Nos	1	1800	500	460	0	2760	**2,760.00**
32	**Manual call point** Supply, Installation, Testing and Commissioning of Manual Call Point (MCP) for fire alarm systems, conforming to relevant IS standards, complete with mounting accessories and wiring, fully tested and operational, installed complete in all respects.	AGNI	Nos	2	130	100	46	0	276	**552.00**
33	**Fire alarm hooter** Supply, Installation, Testing and Commissioning of Hooter for fire alarm system, complete with mounting accessories and wiring, fully tested and operational, installed complete in all respects.	AGNI	Nos	2	160	100	52	0	312	**624.00**
34	**Smoke detector** Supply, Installation, Testing and Commissioning of Smoke Detectors suitable for fire alarm and safety systems, complete with necessary accessories, terminations, and supports, fully tested and operational, installed complete in all respects.	AGNI	Nos	10	250	100	70	0	420	**4,200.00**
35	**Two-core fire alarm cable** Supply, Installation, Testing and Commissioning of 2 Core 1 Sq. mm stranded flexible cable, suitable for fire alarm and safety systems, complete with necessary accessories, terminations, and supports, fully tested and operational, installed complete in all respects. **Core count: 2** **Conductor cross-section: 1 sq. mm**	Unbranded	Mtrs	150	58	35	18.6	0	111.6	**16,740.00**
36	**Fire safety signage lot** Supply, Installation, Testing and Commissioning of fire safety Signages, made of durable material with clear markings, complete with mounting accessories, fully visible, compliant with relevant standards, and installed complete in all respects.	Unbranded	Lot	1	6500	500	1400	0	8400	**8,400.00**

Sr. No.	DESCRIPTION	MAKE / MODEL	UNIT	Qty.	Supply	Installation	20%	Miscellaneous	Rate	Amount
	Core cutting Supply, Installation, Testing and Commissioning of core cutting works, including drilling or cutting of walls, floors, or slabs as required for installation of fire safety equipment, complete with debris removal, safety measures, and restoration, executed in all respects.(if Required)	Unbranded								
37	**Nominal diameter: 125 mm**		Nos	1	0	580	116	0	696	**696.00**
38	**Nominal diameter: 100 mm**		Nos	1	0	460	92	0	552	**552.00**
39	**Nominal diameter: 65 mm**		Nos	1	0	380	76	0	456	**456.00**
								TOTAL OF FIRE APPLIANCES		**34,980.00**

Currency: INR. Supply, installation, markup amount, miscellaneous and rate are per unit. Markup percentages appear in the header or beside mixed-line amounts. Validity: 7 days.

Subtotal	9,41,097.20
Line discounts	0.00
Additional discount	0.00
Tax	0.00
Rounding adjustment	0.00
GRAND TOTAL (INR)	**9,41,097.20**

Terms and conditions / exclusions

1. GST: 18% Goods & Services Tax will be charged extra, as applicable.
2. Quotation Validity: This quotation is valid for 7 days from the date of issue.
3. Civil Works: Any civil work, including excavation, pedestal construction, RCC road cutting, and backfilling, is not included unless specifically agreed.
4. Cabling: Supply of cabling from main source (GEB/Generator) to our panel is in your scope.
5. Documentation Charges: Any legal or statutory fees for approvals, NOC, or related documentation are in your scope.
6. Installation Works: Piping and cabling will be invoiced based on actual installation executed.
7. Payment Terms:

50% advance with Work Order

30% after materials reach your site

15% upon completion of installation

5% after final testing and issuance of NOC

8. NOC Charges: AMC and NOC consultancy charges amounting to 50,000 shall be paid in extra. This amount is not included in the above BOQ and will be charged separately.
9. Site Utilities: Necessary provisions like water and electricity for work or testing to be provided by the client.
10. Invoicing: Invoices will be prepared based on actual measurements. Final invoice will be submitted after full payment is received.

Delivery terms

Delivery and installation schedule to be agreed with the customer.

Bank details

Demo only. Use verified bank details in the quotation document settings.

For FIRE RELIEF SERVICES

Demo authorized signatory
Authorized signatory